

## SECTION 01010

### SUMMARY OF WORK

#### PART 1 GENERAL

##### 1.01 WORK COVERED BY CONTRACT DOCUMENTS

- A. Furnish all labor, equipment and materials to demolish two existing wet pit/dry pit wastewater pump stations, install two new submersible wastewater pump stations with control systems, remove/replace control systems at two additional existing pump stations throughout North Bay Village, and provide four (4) trailer mounted diesel engine driven generators. The project will include but not be limited to all demolition, pump station installation, controls, SCADA, electrical, gravity sewer, sanitary manholes, force main piping and fittings, start-up services, training, site restoration and all other appurtenances necessary for a complete and accepted project. Construction of this project will require close coordination with the Owner and Engineer.
- B. Contractor's Duties:
1. Except as specifically noted, provide and pay for:
    - a. Mobilization and demobilization
    - b. Labor, materials, and equipment
    - c. Tools, construction equipment, and fuel
    - d. Electric, water and utilities required for construction
    - e. Temporary utilities, provisions, and controls
    - f. Freight, sales tax, and permit fees
    - g. Maintenance of traffic
    - h. Surveying, field engineering
    - i. Record drawing information in a format acceptable to the Engineer.
    - j. Compliance with all the conditions of the permits issued and required for this project.
    - k. Construction dewatering
    - l. Wastewater bypass pumping

##### 1.02 CONTRACTS

- A. Construct the work under a Lump Sum or Unit Price as indicated in the Contract Documents.
- B. Subcontractors work directly for the Contractor.

**1.03 WORK BY OTHERS AND FUTURE WORK**

- A. The Owner reserves the right to add or delete Work in accordance with the Contract.

**1.04 CONTRACTOR-FURNISHED PRODUCTS AND RESPONSIBILITIES**

- A. Products furnished to the site and paid for by Contractor:
  - 1. All products necessary to complete the work described herein these contract documents and specifications.
- B. Contractor's Responsibilities:
  - 1. Review and incorporate Owner-reviewed shop drawings, product data, and samples into the construction of the project.
  - 2. Prepare, apply for, and obtain permits that are specified to be obtained by the contractor.
  - 3. Receive and unload products at site; inspect for completeness or damage jointly with Owner.
  - 4. Repair or replace items damaged after receipt.
  - 5. Arrange and pay for product delivery to site.
  - 6. Handle, store, install, and delivered products.
  - 7. Submit claims for transportation damage and replace damaged, defective, or deficient items.
  - 8. Arrange for manufacturers' warranties, inspections, and service.

**1.05 CONTRACTORS USE OF THE PREMISES**

- A. Details of the construction sequence will be discussed and decided at the Pre-Work Conference. Certain areas may be assigned priority to accommodate Owner's interest.

- B. All work shall be within the limits of North Bay Village right-of-way. Contractor shall be responsible for maintenance of traffic when working within the public rights of way.
- C. The staging area locations and costs are the responsibility of the contractor but must be coordinated with North Bay Village. The contractor shall always maintain access to North Bay Village facilities. The contractor shall restore the staging area to an equal or better condition than previously existed upon completion of the work.
- D. The Contractor shall be fully responsible for the safety and security of the construction area including any temporary measures required to maintain its protection. The Contractor will be responsible for any damages or theft incurred to his tools, equipment, machinery, and new work in-place not yet been fully accepted by the Owner.

**PART 2 PRODUCTS**

- A. Not Used

**PART 3 EXECUTION**

- A. Not Used

**END OF SECTION**